

9.0 Guidelines for Best Management Practices

9.1 GENERAL

The purpose of this document is to provide minimum design parameters for certain Best Management Practices (BMPs) for storm water quality features for new development and significant redevelopment. Use of the BMPs presented here does not guarantee acceptance of a particular Storm Water Pollution Prevention Plan (SWP3) or the effectiveness of the BMP to reduce pollutants. Other BMPs may be acceptable on a case-by-case basis. The SWP3 should include the implementation and maintenance of structural and non-structural best management practices to reduce pollutants in storm water runoff from residential, commercial and industrial areas and construction sites. The SWP3 and BMPs shall be prepared and designed in accordance with TCEQ and other regulatory guidelines. The BMPs described in the document are intended to facilitate the plan review process for new development and significant redevelopment projects within the City of Sugar Land.

9.2 DEFINITIONS

Best Management Practices (BMPs) - means activities, practices, and procedures to prevent or reduce the discharge of pollutants directly or indirectly into the municipal storm sewer system, waters in the state, and waters of the United States. Best management practices include:

- (1) Public education;
- (2) Treatment facilities to remove pollutants from storm water;
- (3) Operating and maintenance procedures;
- (4) Facility management practices to control:
 - (a) waste containment and disposal;
 - (b) spillage or leaks of non-storm water;
 - (c) drainage from materials storage, and
 - (d) storm water runoff;
- (5) Erosion and sediment control practices for any land disturbing or construction activities; and
- (6) Prohibition of specific activities, practices, and procedures identified in this article and the federal and state laws, rules and regulations

Construction Site Operator - The person or persons associated with a small or large construction project that meets either of the following two criteria:

- (a) the person or persons that have operational control over construction plans and specifications (including approval of revisions) to the extent necessary to meet the requirements and conditions of this general permit; or
- (b) the person or persons that have day to day operational control of those activities at a construction site that are necessary to ensure compliance with a storm water pollution prevention plan for the site or other permit conditions (e.g. they are authorized to direct workers at a site to carry out activities required by the Storm Water Pollution Prevention Plan or comply with other permit conditions).

Final Stabilization - A construction site where either of the following conditions are met:

- (a) All soil disturbing activities at the site have been completed and a uniform (e.g., evenly distributed, without large bare areas) perennial vegetative cover with a density of 70% of the native background vegetative cover for the area has been established on all unpaved areas and areas not covered by permanent structures, or equivalent permanent stabilization measures (such as the use of riprap, gabions, or geotextiles) have been employed.
- (b) For individual lots in a residential construction site by either:
 - (1) The homebuilder completing final stabilization as specified in condition (a) above; or
 - (2) the homebuilder establishing temporary stabilization for an individual lot prior to the time of transfer of the ownership of the home to the buyer and after informing the homeowner of the need for, and benefits of, final stabilization.
- (c) For construction activities on land used for agricultural purposes (e.g. pipelines across crop or range land), final stabilization may be accomplished by returning the disturbed land to its preconstruction agricultural use. Areas disturbed that were not previously used for agricultural activities, such as buffer strips immediately adjacent to a surface water and areas which are not being returned to their preconstruction agricultural use must meet the final stabilization conditions of condition (a) above.

Illicit Connection – Any manmade conveyance connecting an illicit discharge directly to a municipal separate storm sewer.

Illicit Discharge – Any non-storm water discharge to a municipal separate storm sewer system, except discharges pursuant to a NPDES Permit, TPDES Permit, or separate authorization, or discharges resulting from emergency fire-fighting activities.

Outfall - For the purpose of this permit, a point source at the point where a municipal separate storm sewer discharges to waters of the United States (U.S.) and does not include open conveyances connecting two municipal separate storm sewers, or pipes, tunnels, or other conveyances that connect segments of the same stream or other waters of the U.S. and are used to convey waters of the U.S.

Point Source - any discernible, confined, and discrete conveyance, including but not limited to, any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, container, rolling stock, concentrated animal feeding operation, landfill leachate collection system, vessel or other floating craft from which pollutants are or may be discharged. This term does not include return flows from irrigated agriculture or agricultural storm water runoff.

Storm Water and Storm Water Runoff –any surface flow, runoff, and drainage consisting entirely of water from any form of precipitation or irrigation and resulting from such precipitation or irrigation.

Storm Water Associated with Construction Activity – Storm water runoff from an area where there is either a large construction activity or a small construction activity.

Structural Control (or Practice) – A pollution prevention practice that requires the construction of a device, or the use of a device, to capture or prevent pollution in storm water runoff. Structural controls and practices may include but are not limited to: wet ponds, bioretention, infiltration basins, storm water wetlands, silt fences, earthen dikes, drainage swales, vegetative lined ditches, vegetative filter strips, sediment traps, check dams, subsurface drains, storm drain inlet protection, rock outlet protection, reinforced soil retaining systems, gabions, and temporary or permanent sediment basins.

9.3 EROSION CONTROL PLAN REQUIREMENTS

An erosion control plan shall contain at a minimum the following items:

- a) The proposed location of Refuse Area
- b) The proposed location of Concrete Washout Area
- c) The proposed location of Chemical Storage Area
- d) The proposed location of Portable Toilets
- e) The proposed location of BMPs
- f) The size of Affected Area
- g) The location of All Outfalls for Stormwater Discharge
- h) The depiction of Drainage area and Flow Pattern
- i) Label the Total Number of Acreage
- j) A Vicinity Map
- k) Contact information for the person responsible for the preparation of the plan.

9.4 BEST MANAGEMENT PRATICES

The SWP3 shall be prepared in accordance with TCEQ guidelines and should include the implementation and maintenance of structural and non-structural best management practices to reduce pollutants in storm water runoff from residential, commercial, industrial and construction sites. Below are recommended best management practices that may include but are not limited to:

- (a) Reinforced Silt Fence
- (b) Stone construction entrance
- (c) Curb Inlet Protection
- (d) Rock Berm
- (e) Wye Inlet Protection
- (f) Erosion Control Blankets
- (g) Dewatering Controls
- (h) Filter Tube Controls
- (i) Concrete Washout Controls

All protective measures identified in the SWP3 must be maintained in effective operating condition. If, through inspections or other means, the construction site operator determines that BMPs are not operating effectively, then the construction site operator shall perform maintenance as necessary to maintain the continued effectiveness of storm water controls, and prior to the next rain event if feasible. Erosion and sediment controls that have been intentionally disabled, run-over, removed, or otherwise rendered ineffective must be replaced or corrected immediately upon discovery. If periodic inspections or other information indicates a control has been used incorrectly, is performing inadequately, or is damaged, then the operator must replace or modify the control as soon as practicable after making the discovery. If sediment escapes the site, accumulations must be removed at a frequency that minimizes off-site impacts, and prior to the next rain event, if feasible. If the construction site operator does not own or operate the off-site conveyance, then the permittee must work with the owner or operator of the property to remove the sediment.

Rock Berm Maintenance - The rock berm shall be inspected every two weeks or after each 1/2" rain event and shall be replaced when the structure ceases to function as intended due to silt accumulation among the rocks, washout, construction traffic damage, etc. When silt reaches a depth equal to one-third of the height of the berm or one foot, whichever is less, the silt shall be removed and disposed of properly. When the site is completely stabilized, the berm and accumulated silt shall be removed and disposed of in an approved manner.

Temporary Stone Construction Entrance/Exit Maintenance - When sediment has substantially clogged the void area between the rocks, the aggregate mat must be washed down or replaced. Periodic re-grading and top dressing with additional stone must be done to keep the efficiency of the entrance from diminishing.

Curb Inlet Protection Maintenance - Inspection shall be made by the contractor and silt accumulation must be removed when depth reaches 2". Contractor shall monitor the performance

of inlet protection during each rainfall event and immediately remove the inlet protections if the stormwater begins to overtop the curb. Inlet protection shall be removed as soon as the site has reached final stabilized.

Silt Fence Maintenance - Inspection shall be made every two weeks and after each 1/2" rainfall. Repair or replacement shall be made promptly as needed. Silt fence shall be removed when the site is completely stabilized so as not to block or impede storm flow or drainage. Accumulated silt shall be removed when it reaches a depth of half the height of the fence. The silt shall be disposed of at an approved site and in such a manner as to not contribute to additional siltation.

Erosion Control Blanket Maintenance - Erosion control blankets should be inspected regularly for bare spots caused by weather or other events. Missing or loosened blankets must be replaced or re-anchored. Check for excess sediment deposited from runoff. Remove sediment and/or replace blanket as necessary. In addition, determine the source of excess sediment and implement appropriate measures to control the erosion. Also check for rill erosion developing under the blankets. If found, repair the eroded area. Determine the source of water causing the erosion and add controls to prevent its reoccurrence.

Dewatering Controls Maintenance - Dewatering controls should be inspected regularly. Dewatering discharge points should be checked for erosion. Eroded areas should be repaired, and erosion controls should be installed to prevent future erosion. Dewatering pumps and sediment controls should be monitored, at least hourly, while pumps are in operation to prevent unauthorized discharge and to catch erosion problems or control failure. Conventional sediment controls should be inspected at least weekly when used for continuous dewatering, because they will become overcome with sediment more quickly than when used to control runoff from storm events. The controls shall be maintained according to the criteria in their respective sections. They should be replaced when they no longer provide the necessary level of sediment removal. Sediment filter bags should be checked to determine if they need replacing. The bags cannot be cleaned or reused. They should be used until they reach the manufacturer's recommended capacity. The entire bag with sediment can be disposed of as solid waste. If a controlled location onsite or a spoil site is available, the bag can be cut open and the sediment spread on the ground. Only the bag is waste in this case.

Filter Tubes Maintenance - Organic filter tubes should be inspected regularly. The filter tube should be checked to ensure that it is in continuous contact with the soil at the bottom of the embedment trench. Closely check for rill erosion that may develop under the filter tubes. Eroded spots must be repaired and monitored to prevent reoccurrence. If erosion under the tube continues, additional controls are needed. Staking shall be checked to ensure that the filter tubes are not moving due to stormwater runoff. Repair and re-stake slumping filter tubes. Tubes that are split, torn or unraveling shall be repaired or replaced. Check the filter tube material to make sure that it has not become clogged with sediment or debris. Clogged filter tubes usually lead to standing water behind the filter tube after the rain event. Sediment shall be removed from behind the filter tube before it reaches half the height of the exposed portion of the tube. When sediment control is no longer needed on the site, the tubes may be split open and the filter material may be used for mulching during establishment of vegetation for final stabilization.

Concrete Washout Maintenance - Concrete waste management controls should be inspected regularly for proper handling of concrete waste. Check concrete washout pits and make repairs as needed. Washout pits should not be allowed to overflow. Maintain a schedule to regularly remove concrete waste and prevent over-filling. If illicit dumping of concrete is found, remove the waste and reinforce proper disposal methods through education of employees.

Per TCEQ requirements, erosion control and stabilization measures must be initiated as soon as practicable in portions of the site where construction activities have temporarily ceased. Stabilization measures that provide a protective cover must be initiated as soon as practicable in portions of the site where construction activities have permanently ceased. Except as provided in (A) through (D) below, these measures must be initiated no more than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased:

- (A) Where the initiation of stabilization measures by the 14th day after construction activity temporarily or permanently ceased is precluded by snow cover or frozen ground conditions, stabilization measures must be initiated as soon as practicable
- (B) Where construction activity on a portion of the site has temporarily ceased, and earth disturbing activities will be resumed within 21 days, temporary erosion control and stabilization measures are not required on that portion of site.
- (C) In arid areas, semiarid areas, and areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased or is precluded by arid conditions, erosion control and stabilization measures must be initiated as soon as practicable. Where vegetative controls are not feasible due to arid conditions, the operator shall install non-vegetative erosion controls. If non-vegetative controls are not feasible, the operator shall install temporary sediment controls as required in Paragraph (D) below.
- (D) In areas where temporary stabilization measures are infeasible, the operator may alternatively utilize temporary perimeter controls. The operator must document in the SWP3 the reason why stabilization measures are not feasible, and must demonstrate that the perimeter controls will retain sediment on site to the extent practicable. The operator must continue to inspect the BMPs at the frequency established in Section III.F.7.(a) for unstabilized sites.

9.5 POST-CONSTRUCTION STORM WATER MANAGEMENT IN NEW DEVELOPMENT AND REDEVELOPMENT

Post-construction storm water management in new and redevelopments should include minimum control measures to control post-construction runoff. The minimum control measures below are acceptable and others may be considered on the case-by-case basis.

Minimum Control Measures:

- a) *Alternative Turnarounds* - Dead end streets in residential subdivisions are usually required to have an acceptable option for vehicles to turnaround, with the circular cul-de-sac being the most common. The amount of impervious cover can be reduced from the standard impervious cul-de-sac. It is acceptable to place a landscaped island in the center of the cul-de-sac turnaround as long as it maintains an acceptable turning radius. Alternative turnarounds can be applied in the design of residential, commercial, and mixed-use development. They may be combined with alternative pavers, bioretention areas, and other techniques in an effort to reduce the runoff from the site.
- b) *Grassed Swales* - A grass swale is a stable turf, parabolic or trapezoidal channel used for water quality or to convey stormwater runoff, which does not rely on the permeability of the soil as a pollutant removal mechanism. Grass swales are used to reduce particulate pollutants due to settling and filtration. Particulate pollutant removal occurs when the low velocities and shallow depths allow particulate settling and the grass blades act to filter runoff from the water quality design storm. Grass swales are best suited to transport and treat stormwater runoff generated from impervious surfaces with small drainage areas. Grass swales can be used wherever soil conditions and slopes permit the establishment and maintenance of a dense stand of vegetative cover. Typically, swales have a minimum bottom width of 2 feet to 10 feet and have a recommended side slope of 4:1.
- c) *Catch Basin Insert* - Catch basins, also known as storm drain inlets and curb inlets, are inlets to the storm drain system. Inserts can be designed to improve water quality by removing oil and grease, trash, debris, and sediment can improve the efficiency of catch basins. Some inserts are designed to drop directly into existing catch basins, while others may require retrofit construction.
- d) *Wet Ponds* - Wet ponds (a.k.a. stormwater ponds, wet retention ponds, wet extended detention ponds) are constructed basins that have a permanent pool of water throughout the year (or at least throughout the wet season). Ponds treat incoming stormwater runoff by allowing particles to settle and algae to take up nutrients. The primary removal mechanism is settling as stormwater runoff resides in this pool, and pollutant uptake, particularly of nutrients, also occurs through biological activity in the pond. Wet ponds are generally on-line, end-of-pipe BMPs. The primary pollutant removal mechanism in a water pond is sedimentation. Significant loads of suspended pollutants, such as metals, nutrients, sediments, and organics, can be removed by sedimentation. Wet ponds can be used at residential, commercial and industrial sites. Wet ponds may be single-purpose facilities, providing only runoff treatment, or they may be incorporated into an extended storage or a detention pond design to also provide flow control.



CITY OF SUGAR LAND LAND DISTURBANCE PERMIT

**RETURN YOUR SUBMITTAL TO THE ENGINEERING DEPARTMENT
(Attn: Development Review Coordinator)**

PROJECT NAME _____

Project Location

Address _____

Description of Project _____

OWNER/AGENT

Contact _____

Address _____

Phone _____ **Fax** _____ **Email** _____

ENGINEER

Contact _____

Address _____

Phone _____ **Fax** _____ **Email** _____

CONTRACTOR

Contact _____

Address _____

Phone _____ **Fax** _____ **Email** _____

SPECIAL CONDITIONS AND /OR COMMENTS:



CITY OF SUGAR LAND

LAND DISTURBANCE PERMIT

LAND DISTURBANCE PERMIT SUBMITTAL REQUIREMENTS:

- **TWO (2)** Completed Permits
- **SUBMITTAL FEES:**
 - ☐ City –NO FEE
- **THREE (3) 24 X 36 PRINTS THAT INCLUDE:**
 - ☐ Engineering Civil design drawings (must be signed & sealed by a Professional Engineer) Including Plat/Site Plan, Grading, Drainage and Erosion Control Plan.
 - ☐ One copy of TCEQ Construction General Permit.
 - ☐ One copy of TCEQ Construction Site Notice.
- No land disturbance activities shall begin until a pre-construction meeting has been conducted with the Engineering Department.
- All works performed within City right-of –way (ROW) shall obtain a ROW Permit issued from the Public Works Department.
- This permit and accompanying construction plans shall remain at the job site at all times.
- Applicant agrees that dirt, mud, debris, materials, etc., deposited in the street right-of-way shall be cleaned/removed to the satisfaction of the City Engineer or his/her designee on a regular basis or as needed.

By signing below, I (the Applicant) acknowledge and agree that the work as described herein shall conform to all local, state and federal laws as well as local ordinances whether specified or not. The granting of this permit does not give authority to violate or cancel the provisions of any site or local law regulating the type of work being performed.

X _____
Signature of Applicant **Date**

Printed Name: _____ **Phone** _____

Office Use:

Circle One
Approved / Denied

By:

Signature

Title

Printed Name:

PLOT TIME:

HYPER-CHLORINATED WATER NOTES

1. HYPER-CHLORINATED WATER SHALL NOT BE DISCHARGED TO THE STORM SEWER OR DRAINAGE SYSTEM UNLESS THE CHLORINE CONCENTRATION IS REDUCED TO 4 PPM OR LESS BY CHEMICALLY TREATING THE DECHLORINATE OR BY ONSITE RETENTION UNTIL NATURAL ATTENUATION OCCURS.
2. DISCHARGE OF HIGH FLOW RATE AND VELOCITIES SHALL BE DIRECTED TO VELOCITY DISSIPATION DEVICES.
3. CHLORINE CAN BURN VEGETATION, SO IT SHOULD NOT BE USED TO WATER VEGETATION THAT IS BEING USED FOR STABILIZATION, VEGETATED FILTERS OR BUFFERS, OR OTHER VEGETATION TO BE PRESERVED.
4. HYPER-CHLORINATED WATER MAY BE DISCHARGED TO AN ONSITE RETENTION AREA UNTIL NATURAL ATTENUATION OCCURS. THE AREA MAY BE A DRY STORMWATER RETENTION BASIN, OR A PORTION OF THE SITE MAY BE GRADED TO FORM A TEMPORARY PIT OR BERMED AREA.
5. NATURAL ATTENUATION OF THE CHLORINE MAY BE AIDED BY AERATION. AIR CAN BE ADDED TO THE WATER BY DIRECTING THE DISCHARGE OVER A ROUGH SURFACE BEFORE IT ENTERS THE TEMPORARY RETENTION AREA OR AN AERATION DEVICE CAN BE PLACED IN THE RETENTION AREA.
6. ONSITE DISCHARGE MAY REQUIRE SEVERAL HOURS TO A FEW DAYS BEFORE THE WATER IS SAFE TO DISCHARGE. THE RATE AT WHICH CHLORINE WILL ATTENUATE IS AFFECTED BY SOIL CONDITIONS AND WEATHER CONDITIONS. ATTENUATION WILL OCCUR QUICKEST DURING WARM, SUNNY, AND DRY PERIODS.

SANITARY WASTE NOTES

1. THE CONTRACTOR SHALL PROVIDE AN APPROPRIATE NUMBER OF PORTABLE TOILETS BASED ON THE NUMBER OF EMPLOYEES USING THE TOILETS AND THE HOURS THEY WILL WORK.
2. SANITARY FACILITIES SHALL BE PLACED ON A MINIMUM OF 50 FEET AWAY FROM STORM DRAIN INLETS, CONVEYANCE CHANNELS OR SURFACE WATERS. IF UNABLE TO MEET THE 50 FOOT REQUIREMENT DUE TO SITE CONFIGURATION, PORTABLE TOILETS SHALL BE A MINIMUM OF 20 FEET AWAY FROM STORM DRAIN INLETS, CONVEYANCE CHANNELS OR SURFACE WATER AND SECONDARY CONTAINMENT SHALL BE PROVIDE IN CASE OF SPILLS.
3. THE LOCATION OF THE PORTABLE TOILETS SHALL BE ACCESSIBLE TO MAINTENANCE TRUCKS WITHOUT DAMAGING EROSION AND SEDIMENT CONTROLS OR CAUSING EROSION OR TRACKING PROBLEMS.
4. SANITARY FACILITIES SHALL BE FULLY ENCLOSED AND DESIGNED IN A MANNER THAT MINIMIZES THE EXPOSURE OF SANITARY WASTE TO PRECIPITATION AND STORMWATER RUNOFF.
5. WHEN HIGH WINDS ARE EXPECTED, PORTABLE TOILETS SHALL BE ANCHORED OR OTHERWISE SECURED TO PREVENT THEM FROM BEING BLOWN OVER.
6. THE COMPANY THAT SUPPLIES AND MAINTAINS THE PORTABLE TOILETS SHALL BE NOTIFIED IMMEDIATELY IF A TOILET IS TIPPED OVER OR DAMAGED IN A WAY THAT THE RESULTS IN A DISCHARGE. DISCHARGED SOLID MATTER SHALL BE VACUUMED INTO A SEPTIC TRUCK BY THE COMPANY THAT MAINTAINS THE TOILETS.
7. THE OPERATOR OF THE MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4) SHALL BE NOTIFIED IF A DISCHARGE FROM THE PORTABLE TOILETS ENTERS THE MS4 OR A NATURAL CHANNEL.
8. SANITARY FACILITIES SHALL NOT BE PERMITTED ON PUBLIC SIDEWALKS, STREETS OR INLETS.

DEBRIS AND TRASH NOTES


1. ALL WASTE SOURCES AND STORAGE AREAS SHALL BE LOCATED A MINIMUM OF 50 FEET AWAY FROM INLETS, SWALES, DRAINAGE WAYS, CHANNELS AND OTHER WATERS, IF THE SITE CONFIGURATION PROVIDES SUFFICIENT SPACE TO DO SO. IN NO CASE SHALL MATERIAL AND WASTE SOURCES BE CLOSER THAN 20 FROM INLETS, SWALES, DRAINAGE WAYS, CHANNELS, AND OTHER WATERS.
2. CONSTRUCTION WASTE AND TRASH SHALL BE STORED IN A MANNER THAT MINIMIZES ITS EXPOSURE TO PRECIPITATION AND STORMWATER RUNOFF.
3. WHENEVER POSSIBLE, MINIMIZE PRODUCTION OF DEBRIS AND TRASH.
4. INSTRUCT CONSTRUCTION WORKERS IN PROPER DEBRIS AND TRASH STORAGE AND HANDLING PROCEDURES.
5. SEGREGATE POTENTIAL HAZARDOUS WASTE FROM NON-HAZARDOUS CONSTRUCTION SITE DEBRIS.
6. PROHIBIT LITTERING BY WORKERS AND VISITORS.
7. POLICE SITE DAILY FOR LITTER AND DEBRIS.
8. ENFORCE SOLID WASTE HANDLING AND STORAGE PROCEDURES.
9. IF FEASIBLE, RECYCLE CONSTRUCTION AND DEMOLITION DEBRIS SUCH AS WOOD, METAL, AND CONCRETE.
10. TRASH AND DEBRIS SHALL BE REMOVED FROM THE SITE AT REGULAR INTERVALS THAT ARE SCHEDULED TO EMPTY CONTAINERS WHEN THEY ARE 90 PERCENT FULL OR MORE FREQUENTLY.
11. GENERAL CONSTRUCTION DEBRIS MAY BE HAULED TO A LICENSED CONSTRUCTION DEBRIS LANDFILL.
12. USE WASTE AND RECYCLING HAULERS/FACILITIES APPROVED BY THE LOCAL MUNICIPALITY.
13. CHIPPING OF TREES AND BRUSH FOR USE SUCH AS MULCH IS PREFERRED ALTERNATIVE TO OFFSITE DISPOSAL.
14. NO WASTE, TRASH, OR DEBRIS SHALL BE BURIED, BURNED OR OTHER WISE DISPOSED OF ONSITE.
15. CLEARLY MARK ON ALL DEBRIS AND TRASH CONTAINERS WHICH MATERIALS ARE ACCEPTABLE. FOREMAN AND/OR CONSTRUCTION SUPERVISOR SHALL MONITOR ONSITE SOLID WASTE STORAGE AND DISPOSAL PROCEDURES DAILY.

SPILL AND LEAK RESPONSE NOTES

1. RECORDS OF RELEASES THAT EXCEED THE REPORTABLE QUANTITY (RQ) FOR OIL AND HAZARDOUS SUBSTANCES SHOULD BE MAINTAINED IN ACCORDANCE WITH THE FEDERAL AND STATE REGULATIONS.
2. EMERGENCY CONTACT INFORMATION AND SPILL RESPONSE PROCEDURES SHALL BE POSTED IN A READILY AVAILABLE REA FOR ACCESS BY ALL EMPLOYEES AND SUBCONTRACTORS.
3. SPILL CONTAINMENT KITS SHOULD BE MAINTAINED FOR PETROLEUM PRODUCTS AND OTHER CHEMICALS THAT ARE REGULARLY ONSITE. MATERIALS IN KITS SHOULD BE BASED ON CONTAINMENT GUIDELINES IN THE MATERIALS SAFETY AND DATA SHEETS (MSDS) FOR THE SUBSTANCE MOST FREQUENTLY ONSITE.
4. SPILL KITS ARE INTENDED FOR RESPONSE TO SMALL SPILLS, TYPICALLY LESS THAN 5 GALLONS, OF SUBSTANCES THAT ARE NOT EXTREMELY HAZARDOUS.
5. SIGNIFICANT SPILLS OR OTHER RELEASES WARRANT IMMEDIATE RESPONSE BY TRAINED PROFESSIONALS.
6. SUSPECTED JOB-SITE CONTAMINATION SHOULD BE IMMEDIATELY REPORTED TO REGULATORY AUTHORITIES AND PROTECTIVE ACTIONS TAKEN.
7. THE CONTRACTOR SHOULD BE REQUIRED TO DESIGNATE A SITE SUPERINTENDENT, FOREMAN, SAFETY OFFICER, OR OTHER SENIOR PERSON WHO IS ONSITE DAILY TO BE THE SPILL AND LEAK RESPONSE COORDINATOR (SLRC) AND MUST HAVE KNOWLEDGE OF AND BE TRAINED IN CORRECT SPILL AND LEAK RESPONSE PROCEDURES.


SUBGRADE STABILIZATION NOTES

1. MINIMIZE THE DISCHARGE OF THE CHEMICAL STABILIZERS BY THE CONTRACTOR LIMITING THE AMOUNT OF STABILIZING AGENT ONSITE TO THAT WHICH CAN BE THOROUGHLY MIXED AND COMPACTED BY THE END OF EACH WORKDAY.
2. STABILIZERS SHALL BE APPLIED AT RATES THAT RESULT IN NO RUN OFF.
3. STABILIZATION SHALL NOT OCCUR IMMEDIATELY BEFORE AND DURING RAINFALL EVENTS.
4. NO TRAFFIC OTHER THAN WATER TRUCKS AND MIXING EQUIPMENT SHALL BE ALLOWED TO PASS OVER THE AREA BEING STABILIZED UNTIL AFTER COMPLETION OF MIXING THE CHEMICAL.
5. AREA ADJACENT AND DOWNSTREAM OF STABILIZED AREAS SHALL BE ROUGHENED TO INTERCEPT CHEMICAL RUNOFF AND REDUCE RUNOFF VELOCITY.
6. GEOTEXTILE FABRICS SUCH AS THOSE USED FOR SILT FENCE SHOULD NOT BE USED TO TREAT CHEMICAL RUNOFF, BECAUSE THE CHEMICALS ARE DISSOLVED IN THE WATER AND WON'T BE AFFECTED BY A BARRIER AND THE SUSPENDED SOLIDS ARE SIGNIFICANTLY SMALLER THAN THE APPARENT OPENING SIZE OF THE FABRIC.
7. IF SOIL STABILIZERS ARE STORED ONSITE, THEY SHALL BE CONSIDERED HAZARDOUS MATERIAL AND SHALL BE MANAGED ACCORDING TO THE CRITERIA OF CHEMICAL MANAGEMENT TO CAPTURE ANY ACCIDENTAL LIME OR CHEMICAL OVERFLOW.
8. THE CONTRACTOR SHALL INSTALL BMP'S TO ALL INLETS AND OPENINGS CONNECTED TO THE STORM SEWER SYSTEMS TO PREVENT LIME FROM ENTERING THE MS4 SYSTEM.

No.	DATE	REVISION
PRELIMINARY FOR REVIEW ONLY		
SEAL:		
DESIGN ENGINEER: _____ DATE _____		
		
CITY OF SUGAR LAND, TEXAS ENGINEERING DEPARTMENT		
CONSTRUCTION PLANS FOR:		
GENERAL EROSION CONTROL NOTES		
JOB No.: DATE: DESIGNED BY: DRAWN BY: CHECKED BY: SCALE:		SL-28 SHEET OF

CAD FILE PATH:
PLOT DATE:

CAD FILE PAID:
PLOT DATE:




- | INLET
OPENING | MINIMUM NUMBER
OF SAND BAGS | |
|------------------|--------------------------------|-------|
| | TOP | FRONT |
| 5' | 2 | 3 |
| 10' | 3 | 3 |
| 15' | 3 | 4 |
| 20' | 4 | 4 |




- NOTE: STONE OVERFLOW STRUCTURES OF OTHER OUTLET CONTROL DEVICES SHALL BE INSTALLED AT ALL LOW POINTS ALONG THE FENCE OR EVERY 300 FEET IF THERE IS NO APPARENT LOW POINT





FILTER FABRIC WYE INLET PROTECTION
N.T.S.





- SILT FENCE
STONE OVERFLOW STRUCTURE
N.T.S.

No.	DATE	REVISION
PRELIMINARY FOR REVIEW ONLY		
SEAL:		
DESIGN ENGINEER: _____ DATE _____		
 <p>CITY OF SUGAR LAND, TEXAS ENGINEERING DEPARTMENT</p>		
<u>CONSTRUCTION PLANS FOR:</u> EROSION CONTROL		
CONSTRUCTION DETAILS - 1		
JOB No.: DATE: DESIGNED BY: DRAWN BY: CHECKED BY: SCALE:	SL-01 SHEET OF	

LOAD FILE PAIR:
PLOT DATE:




DEWATERING CONTROLS
N.T.S.



ORGANIC FILTER TUBE PERIMETER CONTROL PROFILE
N.T.S.

FILTER TUBE
N.T.S.




CONCRETE WASHOUT NOTES

1. SANDBAGS MAYBE REPLACED BY A SOIL BERM TO ANCHOR THE PLASTIC BAG

CONCRETE WASHOUT AREA
N.T.S.



1. TYPE OF NETTING, FILTER MATERIAL, DIAMETER OF TUBE, AND SPACING OF TUBES SHALL BE SPECIFIED BY THE DESIGNER BASED ON THE FOLLOWING SITE PARAMETERS:
 - SIZE OF CONTRIBUTING DRAINAGE AREA
 - STEEPNESS OF SLOPE
 - GROUND CONDITIONS (SOIL OR PAVEMENT)
2. DESIGNER SHALL SHOW ON THE DRAWINGS THE LOCATIONS WHERE TUBE ARE TO BE TURNED UPSLOPE. UPSLOPE LENGTHS SHALL BE MINIMUM OF 10 FEET.

No.	DATE	REVISION			
PRELIMINARY FOR REVIEW ONLY					
SEAL:					
_____ DATE _____					
DESIGN ENGINEER:					
					
CITY OF SUGAR LAND, TEXAS ENGINEERING DEPARTMENT					
<u>CONSTRUCTION PLANS FOR:</u>					
EROSION CONTROL DETAILS - 2					
JOB No.: DATE: DESIGNED BY: DRAWN BY: CHECKED BY: SCALE:		SL-30 SHEET OF			